

## Exterior Lines of T. 4 S., R. 31 E. W.M.

Chains		Feet
43.00	Enter timber, course N.W. and S.E.	
60.00	New house, W. about 12 Chs.	
80.00	Set basalt stone 16 x 10 x 6 on level for Cor. to Secs. 13, 24, 18 and 19.	
	A Pine 16 ins. diam. brs. N. 24° E. 40 lks. dist.	
	" " 36 " " " S. 38° E. 58 lks. dist.	
	" " 16 " " " S. 70° W. 70 lks. dist.	
	" " 24 " " " N. 54° W. 75 lks. dist.	
	Land; surface undulating, Soil; 1st and 2nd rate. Some Pine timber on N. $\frac{1}{2}$ mile good grass. Good farming land.	
	<hr/>	
	N. on the E. Bdy. of Sec. 13,	
		Var. 19°45'E
32.00	Leave timber, E. and W.	
40.00	Set basalt stone 17 x 12 x 8 on slight S.W. slope in open glade, for $\frac{1}{4}$ Sec. Cor.	
67.00	Enter timber, course S.E. and N.W.	
75.00	Begin ascent of mountains	
80.00	Set basalt stone 15 x 10 x 10 on S. face of ridge in mound of stone for Cor. to Secs. 12, 13, 7 and 18.	
	A Pine 12 ins. diam. brs. N. 68° E. 162 lks. dist.	
	" " 18 " " " S. 80° E. 107 lks. dist.	
	" " 40 " " " S. 62° W. 121 lks. dist.	
	Land; surface undulating, Soil; 1st and 2nd rate. Good grass. Some Pine timber, excellent farming land.	
		October 19, 1880
	<hr/>	
	N. on the E. Bdy. of Sec. 12,	
		Var. 20° 00'E.
40.00	A Pine 12 ins. diam. on S. face of ridge for $\frac{1}{4}$ Sec. Cor.	
	A Pine 8 ins. diam. brs. N. 47° E. 58 lks. dist.	
	" " 18 " " " S. 82° W. 20 lks. dist.	
80.00	A Fir 14 ins. diam. on W. slope for Cor. to Secs. 1, 12,	