

Subdivisional Lines of T. 4 S., R. 31 E. W.M.

Chains		Feet
40.00	Set Post for Temp. $\frac{1}{4}$ Sec. Cor.	
80.12	Intersected E. Bdy 14 lks. N. of Cor. to Secs. 24, 25, from which Cor. I run, N. $89^{\circ} 54'$ W. on a true line bet. Secs. 24 and 25, Var. $19^{\circ} 45'$ E.	
40.06	Set basalt stone 20 x 12 x 10 in Sag for $\frac{1}{4}$ Sec. Cor. A Pine 8 ins. diam. brs. N. $6^{\circ}$ E. 140 lks. dist.	
43.00	Wagon road, course N.E. and S.W.	
80.12	The Cor. to Secs. 23, 24, 25 and 26. Land; surface undulating, Soil; 2nd and 1st rate. Some scattering groves of Pine timber, excellent grass. Good farming land, nearly all of Sec. 25 in good farming land. Oct. 21, 1880	
<hr/> N. bet. Sec. 23 and 24, Var. $19^{\circ} 45'$ E.		
25.00	Foot of knoll, S.E. and N.W.	
40.00	Set basalt stone 20 x 12 x 4 in mound of stone, on S face of knoll for $\frac{1}{4}$ Sec. Cor.	+100
50.00	Foot of knoll, N.E. and S.W.	
65.50	Metteer's house brs. W. 60 lks.	
80.00	Set balm post on level for Cor. to Secs. 13, 14, 23 & 24. A Pine 28 ins. diam. brs. N. $40^{\circ}$ E. 38 lks. dist. " Balm 6 " " " S. $46^{\circ}$ E. 56 " " " " 6 " " " S. $22^{\circ}$ W. 42 " " " Pine 20 ins. diam. brs. N. $63^{\circ}$ W. 100 lks. dist. Land; surface level except knoll, Soil; 1st and 2nd rate, scattering Pine timber. Good grass. Excellent farming land.	-130
<hr/> E. on a random line bet. Secs. 13 and 24. Var. $20^{\circ} 30'$ E.		
40.00	Set post for temp. $\frac{1}{4}$ Sec. Cor.	
80.36	Intersected E. Bdy., 26 lks. N. of Cor. to Secs. 13 and 24, from which Cor. I run,	