

Subdivisional Lines of T. 4 S., R. 31 E., W.M.

| Chains | | Feet |
|--------|--|------|
| 40.08 | Set basalt stone 17 x 10 x 8 in mound of stone on level for $\frac{1}{4}$ Sec. Cor. A Pine 12 ins. diam. brs. N. 57° W., 104 lks. dist. | |
| 80.16 | The Cor. to Secs. 21, 22, 27 and 28. Land; surface undulating, Soil; 3rd and 2nd rate, some scattering Pine timber but mostly open. Good grass. Sec. 27 has a large part good farming land. | |
| | N. bet. Secs. 21 and 22. Var. 20° 50' E. | |
| 7.50 | Snipe Creek, 20 lks. wide, course S.W. | |
| 40.00 | Set basalt stone 20 x 8 x 8 on level for $\frac{1}{4}$ Sec. Cor. | |
| 80.00 | Set Tamarack post 4 ins. sq. and 4 ft. long, dug pits and raised mound on level for Cor. to Secs. 15, 16, 20 and 21. Land; surface nearly level, Soil; 1st rate, small part 2nd rate on S. $\frac{1}{2}$ mile. good grass. Excellent farming land. | |
| | E. on a random line bet. Sec. 15 and 22, Var. 21° 00' E. | |
| 40.00 | Set post for temp. $\frac{1}{4}$ Sec. Cor. | |
| 79.95 | Intersected N. and S. line, 12 lks. N. of Cor. to Secs. 14, 15, 22 and 23 from which Cor. I run, N. 89° 55' W. on a true line bet. Sec. 15 and 22. Var. 20° 30' E. | |
| 39.97 | Set Tamarack post, dug pits and raised mound for $\frac{1}{4}$ Sec. Cor. | |
| 43.50 | Snipe Creek, 15 lks. wide, course S. | |
| 79.95 | The Cor. to Secs. 15, 16, 21 and 22. Land; surface nearly level, Soil; 1st rate, good grass. Excellent farming land. Sec. 22 is nearly all good farming land. | |
| | October 25, 1880 | |