

Subdivisional of T. 4 S., R. 31 E., W.M.

| Chains | | Feet |
|--------|--|------|
| | Var. 18° 45' E. | |
| 40.00 | Set basalt stone 17 x 12 x 5 on E. slope for $\frac{1}{4}$ Sec. Cor. A Pine 22 ins. diam. brs. S. 23° E. 156 lks. dist. No tree W. | |
| 78.00 | Leave timber, course E. and W. | |
| 80.00 | Set basalt stone 20 x 9 x 7 in mound of stone on E. slope for Cor. to Secs. 7, 8, 17 and 18. A Pine 16 ins. diam. brs. N. 5° E. 306 lks. dist. A Pine 28 ins. diam. brs. S. 64° W. 287 lks. dist. No other trees near. Land; surface slightly rolling, Soil; 3rd and 2nd rate. Mostly heavy Pine, Fir and Tamarack timber. Good grass in openings. | |
| | E. on a random line bet. Sec. 8 and 17, | |
| | Var. 18° 15' E. | |
| 40.00 | Set post for temp. $\frac{1}{4}$ Sec. Cor. | |
| 80.28 | Intersected N. and S. line, 18 lks. S. of Cor. to Secs. 8, 9, 16 and 17, from which Cor. I run, S. 89° 52' W. on a true line bet. Secs. 8 and 17, | |
| | Var. 20° 30' E. | |
| 40.14 | Set basalt stone 16 x 12 x 8 in Sag for $\frac{1}{4}$ Sec. Cor. A Pine 22 ins. diam. brs. N. 30° E. 15 lks. dist. A Fir 15 ins. diam. brs. S. 42° E. 35 lks. dist. | |
| 62.00 | Leave timber, course N. and S. | |
| 80.28 | The Cor. to Sec. 7, 8, 17 and 18. Land; surface rolling, Soil; 2nd and 3rd rate, heavy timber except W. 18 Chs. & a few small glades. Pine, Tamarack and Fir. Some grass. Oct. 29, 1880 | 1100 |
| | W. on a random line bet. Sec. 7 and 18. | |
| | Var. 18° 15' E. | |
| 40.00 | Set post for temp. $\frac{1}{4}$ Sec. Cor. | |
| 79.55 | Intersected W. Bdy. 52 lks. N. of Cor. to Secs. 7 and 18, | |