

## Exterior Lines, T. 5 S., R. 32 E., W. M.

| Chains |  |
|--------|--|
|        | A pine, 8 ins. diam., brs. S.52°E., 27 lks. dist.  |
|        | AA " 8 " " " S.53°W., 22 " "   |
|        | A " 5 " " " N.38°W., 14 " "  |
|        | Land; surface undulating.  |
|        | Soil; 1st & 2nd rate.  |
|        | Heavy pine & tamarack timber on E. 50 chs. Good grass on open land. Mostly good farming land.  |
|        | N.89°43'E. on true line along the N. Bdy. of Sec. 4.<br>Var.19°30'E.   |
| 24.00  | Leave heavy timber, course N. & S.   |
| 40.00  | Set pine post, in ground, for $\frac{1}{4}$ Sec. Cor., on level.<br>A pine, 10 ins. diam., brs. S.11°W., 286 lks. dist.<br>No tree N.  |
| 80.00  | Set basalt stone, 16 x 10 x 4 on level, in swale, for Cor. to Secs. 3, 4, 33 & 34.<br>A pine, 6 ins. diam., brs. N.38°E., 123 lks. dist.<br>A " 6 " " " S.74°E., 133 " "<br>A " 5 " " " S.50°W., 110 " "<br>A " 5 " " " N.18°W., 122 " " |
|        | Land; surface undulating.  |
|        | Soil; 2nd & 3rd rate.  |
|        | Pine timber with openings of prairie. Good grass in open glades. Mostly good farming land.   |
|        | N.89°43' E. on true line along N. Bdy. of Sec. 3.<br>Var.18°45'E.  |
| 40.00  | Set basalt stone, 12 x 10 x 5, in mound of stone, on slight S.W. slope for $\frac{1}{4}$ Sec. Cor.   |
| 80.00  | Set basalt stone, 14 x 12 x 4, in mound of stone, on S. slope for Cor. to Secs. 2, 3, 34 & 35.<br>A pine, 6 ins. diam., brs. N.88°E., 76 lks. dist.<br>A " 11 " " " S.31°E., 165 " "   |
|        | Land; surface undulating.  |
|        | Soil; 2nd & 3rd rate.  |
|        | Occasional groves of pine timber. Good grass. Some good farming land.  |