

## Exterior Lines, T. 5 S., R. 32 E., W. M.

Chains	N. 89°43'E. on true line along N. Bdy. of Sec. 2. Var. 20°00'E.
40.00	Set basalt stone, 18 x 10 x 8 ins., in mound of stone, on S. slope for $\frac{1}{4}$ Sec. Cor.
80.00	Set basalt stone, 14 x 12 x 5 & post, in mound of stone, on S. slope for Cor. to Secs. 1, 2, 35 & 36. Land; surface undulating. Soil; 2nd & 3rd rate. Good grass. Some good farming land.
	N. 89°43'E. on true line along N. Bdy. of Sec. 1. Var. 21°00'E.
11.50	Ravine, course S.W. and enter timber.
40.00	Set basalt stone, 20 x 14 x 5 on steep S.E. face of creek bluff for $\frac{1}{4}$ Sec. Cor. A pine, 10 ins. diam., brs. S. 25 lks. dist. No tree on N.
49.50	Camas Creek, 40 lks. wide, course S.W.
66.50	On bluff & leave timber, N.E. & S.W.
80.00	The Cor. to Tps. 4 & 5 S., Rs. 32 & 33 E. Land; surface very broken except E. 14 chs. Soil; 3rd & small part 2nd rate. Mostly heavy pine, tamarack & fir timber. Good grass in green openings. May 31, 1881.
	Subdivisional Lines, T. 4 S., R. 32 E., W. M. As surveyed by George S. Pershin, U.S. Deputy Surveyor, Under Contract No. 390, Dated May 12, 1881.
	N. bet. Secs. 35 & 36. Var. 21°00'E.
40.00	Set basalt stone, 16 x 10 x 6, on S. slope, in mound of stone, for $\frac{1}{4}$ Sec. Cor.
72.00	Enter timber, course S.E. & N.W.
80.00	Set basalt stone, 18 x 12 x 4 on E. slope, for Cor. to Secs. 25, 26, 35 & 36. A pine, 16 ins. diam., brs. N. 36°E., 59 lks. dist.