

Subdivisional Lines, T.4 S., R.32 E., W. M.

Chains	E. on random line bet. Secs. 24 & 25. Var.18°45'E.
40.00	Set post for temp. $\frac{1}{4}$ Sec. Cor.
79.04	Intersected E. Bdy., 12 lks. N. of Cor. to Secs. 24 & 25, from which Cor., I run N.89°55'W. on true line bet. Secs. 24 & 25. Var.19°45'E.
39.52	Set basalt stone, 15 x 12 x 5 on slight W. slope for $\frac{1}{4}$ Sec. Cor. A pine, 8 ins. diam., brs. N.16°E., 114 lks. dist. A " 22 " " " S.58°E., 26 " "
79.04	The Cor. to Secs. 23, 24, 25 & 26. Land; surface rolling. Soil; 2nd & 3rd rate. Heavy pine, tamarack & fir timber, with open glades. June 15, 1881
	N. bet. Secs. 23 & 24. Var.18°45'E.
40.00	Set basalt stone, 14 x 12 x 5, on level, for $\frac{1}{4}$ Sec. Cor. A pine, 8 ins. diam., brs. N.18°E., 69 lks. dist. A " 22 " " " S.58°E., 59 " "
80.00	Set basalt stone, 18 x 10 x 5 ins., in open glade on slight S. slope, for Cor. to Secs. 13, 14, 23 & 24. A pine, 11 ins. diam., brs. N.50°E., 125 lks. dist. A " 12 " " " S.64°E., 88 " " A " 12 " " " S.36°W., 188 " " No tree N.W. Land; surface rolling. Soil; 3rd & 2nd rate. Heavy pine, tamarack & fir timber, with open glades. Some willow & young timber underbrush.
	E. on random line bet. Secs. 13 & 24. Var.18°15'E.
40.00	Set post for temp. $\frac{1}{4}$ Sec. Cor.