

Subdivisional Lines, T.4 S., R.32 E., W. M.

Chains	<p>Land; surface nearly level. Soil; 1st & 2nd rate. Good grass on prairie. Pine timber on S. 27 chs.</p>
	<p>E. on random line bet. Secs. 28 & 33. Var. 21°40'E.</p>
40.00	Set post for temp. $\frac{1}{4}$ Sec. Cor.
80.70	<p>Intersected N. & S. line, 14 lks. S. of Cor. to Secs. 27, 28, 33 & 34, from which Cor., I run S. 89°54'W. on true line bet. Secs. 28 & 33.</p>
40.35	<p>Set basalt stone, 18 x 14 x 10 on slight W. slope, in strip of of timber, for $\frac{1}{4}$ Sec. Cor. A pine, 5 ins. diam., brs. N. 74°E., 93 lks. dist. A " 10 " " " S., 161 " "</p>
80.70	<p>The Cor. to Secs. 28, 29, 32 & 33. Land; surface rolling. Soil; 1st & 2nd rate. Some scattering groves of pine timber. Good grass. Good farming land. June 22, 1881.</p>
	<p>N. bet. Secs. 28 & 29. Var. 21°40'E.</p>
	Jane Hick's house brs. N. 58°W.
40.00	<p>Set basalt stone, 14 x 10 x 6, on S.W. slope, for $\frac{1}{4}$ Sec. Cor. A pine, 20 ins. diam., brs. S. 18°E., 61 lks. dist. A " 24 " " " S. 45°W., 168 " "</p>
	James Hick's house brs. S. 75°W.
80.00	<p>Set basalt stone, 20 x 12 x 5, on mound of stone, on W. slope, for Cor. to Secs. 20, 21, 28 & 29. Land; surface rolling. Soil; 1st, 2nd & 3rd rate. A scattering grove of pine, near $\frac{1}{4}$ Sec. Cor. Good grass. Large part good farming land.</p>