

Subdivisional Lines, T.4 S., R.32 E., W. M.

Chains	
	E. on random line bet. Secs. 21 & 28. Var. 20°30'E.
40.00	Set post for temp. 1/4 Sec. Cor.
80.50	Intersected N. & S. line, 12 lks. South of Cor. to Secs. 21, 22, 27 & 28, from which Cor., I run S.89°55'W. on true line bet. Secs. 21 & 28. Var. 20°30'E.
40.25	Set basalt stone, 14 x 12 x 4, on slight N.W. slope for 1/4 Sec. Cor. A pine, 9 ins. diam., brs. N.68°E., 44 lks. dist. A pine, 10 ins. diam., brs. S.83°W., 108 lks. dist.
48.00	Leave timber, courses S.E. & N.W.
80.50	ThavCor. to Secs. 20, 21, 28 & 29. Land; surface rolling. Soil; 2nd & 3rd rate. Good grass; Pine timber on E. 48 chs.
<hr/>	
	N. bet. Secs. 20 & 21. Var. 20°30'E.
24.00	Enter timber, course S.E. & N.W.
35.00	Owens Creek, 25 lks. wide, course W.
40.00	Set basalt stone, 14 x 12 x 6, on S. slope, for 1/4 Sec. Cor. A fir, 8 ins. diam., brs. S. 23°E., 53 lks. dist. A fir, 16 ins. diam., brs. S.12°W., 69 lks. dist.
72.00	Large open glade.
80.00	Set basalt stone, 20 x 10 x 8, and post, in mound of stone, on South-west slope for Cor. to Secs. 16, 17, 20 and 21. A pine, 32 ins. diam., brs. N.56°E., 213 lks. dist. No other trees near. Land; surface broken. Soil; 3rd & 2nd rate.