

## Exterior Lines, T.4 S., R.33 E., W. M.

|        |  |
|--------|--|
| Chains | <p>marked <math>\frac{1}{4}</math> on N. face.</p> <p>A tamarack, 8 ins. diam., brs. N.76°W., 15 lks. dist., marked <math>\frac{1}{4}</math> S., B.T.</p> <p>A tamarack, 5 ins. diam., brs. S., 24 lks. dist. marked <math>\frac{1}{4}</math> S., B.T.</p>   |
| 80.00  | <p>Set basalt stone, 16 x 12 x 7 ins., 11 ins. in ground, for Cor. to Secs. 32, 33, 4 &amp; 5, marked with 2 notches on W. and 4 notches on E. edges, 80 ft. descent.</p> <p>A fir, 18 ins. diam., brs. N.20°E., 25 lks. dist., marked T.4 S., R.33 E., S.33, B.T.</p> <p>A pine, 11 ins. diam., brs. S.14°E., 30 lks. dist., marked T.5 S., R.33 E., S.4, B.T.</p> <p>A pine, 6 ins. diam., brs. S.20°W., 27 lks. dist., marked T.5 S., R.33 E., S.5, B.T.</p> <p>A pine, 10 ins. diam., brs. N.68°W., 38 lks. dist., marked T.4 S., R.33 E., S.32, B.T.</p> <p>Land; surface rolling .</p> <p>Soil; 2nd &amp; 3rd rate.</p> <p>Mostly heavy pine, tamarack &amp; fir timber, with open glades.</p> |
|        | <p>S.89°51'E. on true line bet. Secs. 33 &amp; 4.</p> <p style="text-align: right;">Var.20°15'E.</p>   |
| 11.20  | Foot of bluff near creek, descent, 180 ft.; spring branch, course N.   |
| 34.50  | Enter open glade.  |
| 40.00  | Set basalt stone, 18 x 10 x 5 ins., 12 ins. in ground, for $\frac{1}{4}$ Sec. Cor., marked $\frac{1}{4}$ on N. face. No trees near, raised mound of stone on N. side, in lieu of pits.   |
| 45.00  | Leave open glade, course N. & S.   |
| 55.00  | Camas Creek, 45 lks. wide, course N.W.   |
| 59.50  | Leave creek bottom and begin ascent, N.W. & S.E.   |
| 66.50  | On spur, extending S. Ascent 60 ft.  |
| 70.00  | Creek bottom, descent 50 ft., open   |
| 80.00  | Set basalt stone, 18 x 8 x 7 ins., 12 ins. in ground, for Cor. to Secs. 33, 34, 3 & 4, marked with 3 notches on E. and 3 notches on W. edges, from which   |