

## Exterior Lines, T.4 S., R.33 E., W. M.

Chains	<p>A pine, 8 ins. diam., brs. S.8°W., 102 lks. dist., marked T.5 S., R.33 E., S.4, B.T.</p> <p>No other trees near.</p> <p>Raised mound of stone alongside of Cor., in lieu of pits. Land; surface part rolling &amp; part level. Soil; 3rd &amp; 2nd rate, and small part on creek bottom 1st rate.</p> <p>Heavy pine, tamarack &amp; fir timber or dense underbrush most of the mile.</p> <hr/> <p>S. 89°51'E. on true line bet. Secs. 34 &amp; 3. Var. 18°30'E.</p> <p>Nearly level surface.</p> <p>.70 Camas Creek, 20 lks. wide, course S.W.</p> <p>40.00 Set basalt stone, 12 x 8 x 6 ins., 9 ins. in ground, for <math>\frac{1}{4}</math> Sec. Cor., marked <math>\frac{1}{4}</math> on N. face. Raised mound of stone alongside in lieu of pits.</p> <p>44.25 Camas Creek, 25 lks. wide, course N.W.</p> <p>80.00 Set basalt stone, 16 x 12 x 5 ins., 11 ins. in ground, for Cor. to Secs. 34, 35, 2 &amp; 3, marked with 4 notches on W. and 2 notches on E. edges, from which</p> <p>A pine, 7 ins. diam., brs. S.64°E., 44 lks. dist., marked T.5 S., R.33 E., S.2, B.T.</p> <p>A pine, 14 ins. diam., brs. S.3°W., 56 lks. dist., marked T.5 S., R.33 E., S.3, B.T.</p> <p>No other trees near.</p> <p>Raised mound of stone alongside Cor., in lieu of pits. Land; surface nearly level. Soil; 2nd &amp; 1st rate. Some groves of thick young pine timber. Mostly good natural meadow.</p> <hr/> <p>S. 89°51'E. on true line bet. Secs. 35 &amp; 2. Var. 20°00'E.</p> <p>1.50 Wagon road to Hot Sulphur Springs, N. &amp; S.</p> <p>1.75 Fence, course N. &amp; S.; brook, 5 lks. wide, course S.</p>
--------	--