

Exterior Lines, T.4 S., R.33 E., W. M.

Chains	
4.00	Cabin about 3 chs. S., claimed by Henry Bowman.
8.00	Fence, course N. & S.; leave sheep yard.
28.50	Creek, 30 lks. wide, course S.W.
37.00	Creek, course N.W., 50 lks. wide.
40.00	Set pine post, 4 ins. diam., & 4 ft. long, on level, for $\frac{1}{4}$ Sec. Cor., marked $\frac{1}{4}$ S. on N. side, from which A pine, 10 ins. diam., brs. N.14°E., 134 lks. dist., marked $\frac{1}{4}$ S., B.T. A pine, 10 ins. diam., brs. S.77°E., 135 lks. dist., marked $\frac{1}{4}$ S., B.T.
73.50	Begin to ascend.
80.00	Set basalt stone, 16 x 14 x 5 ins., 11 ins. in ground, on slight S.W. slope, for Cor. to Secs. 35, 36, 1 & 2, marked with 1 notch on E. and 5 notches on W. edges. Ascent 35 ft. A pine, 20 ins. diam., brs. N.52°E., 160 lks. dist., marked T.4 S., R.33 E., S.36, B.T. A pine, 44 ins. diam., brs. S.46°E., 126 lks. dist., marked T.5 S., R.33 E., S.1, B.T. A pine, 30 ins. diam., brs. S.16°W., 27 lks. dist., marked T.5 S., R.33 E., S.2, B.T. No tree N.W. Raised mound of stone alongside in lieu of pits. Land; surface nearly level. Soil; 1st & 2nd rate. Mostly open creek bottom. Some pine timber on E. $\frac{1}{2}$ mile.
	S.89°51' E. on true line bet. Secs. 36 & 1. Var. 18°15' E.
	Cabin brs. S.
8.00	" " S.41°W., along S. slope.
40.00	Set basalt stone, 18 x 10 x 8 ins., 12 ins. in ground, on S.E. slope, for $\frac{1}{4}$ Sec. Cor., marked $\frac{1}{4}$ on N. face, from which A pine, 18 ins. diam., brs. N.64°E., 29 lks. dist., marked $\frac{1}{4}$ S. B. M.