

## Exterior Lines, T.4 S., R.33 E., W. M.

Chains	N. on E. Bdy. of Sec. 12. Var. 20°00'E. Heavy timber.
40.00	Set basalt stone, 16 x 14 x 10 ins., 11 ins. in ground, for $\frac{1}{4}$ Sec. Cor., marked $\frac{1}{4}$ on W. face. A pine, .7 ins. diam., brs. N.82°E., 34 lks. dist., marked $\frac{1}{4}$ S., B.T. A pine, 7 ins. diam., brs. S.82°W., 12 lks. dist., marked $\frac{1}{4}$ S., B.T.
59.75	A spring branch, course N.W.
80.00	Set basalt stone, 20 x 10 x 5 ins., 14 ins. in ground, for Cor. to Secs. 1, 12, 6 & 7, marked with 5 notches on S. and one notch on N. edges. A pine, 18 ins. diam., brs. N.26°E., 78 lks. dist., marked T.4 S., R.34 E., S.6, B.T. A fir, 10 ins. diam., brs. S.62°E., 110 lks. dist., marked T.4 S., R.34 E., S.7, B.T. A fir, 28 ins. diam., brs. S.40°W., 23 lks. dist., marked T.4 S., R.33 E., S.12, B.T. A fir, 10 ins. diam., brs. N.72°W., 117 lks. dist., marked T.4 S., R.33 E., S.1, B.T. Land; surface undulating. Soil; 3rd, 2nd & 1st rate. Heavy pine, tamarack and fir timber, with open glades.
	N. on E. Bdy. of Sec. 1. Var. 20°45'E.
22.00	Begin descending.
40.00	Set basalt stone, 14 x 12 x 4 ins., 10 ins. in ground, for $\frac{1}{4}$ Sec. Cor., marked $\frac{1}{4}$ on W. face. A pine, 10 ins. diam., brs. N.34°E., 81 lks. dist., marked $\frac{1}{4}$ S., B.T. A pine, 12 ins. diam., brs. N.38°W., 90 lks. dist., marked $\frac{1}{4}$ S., B.T.
47.50	A stream, 15 lks. wide, course N.E. Descent 180 ft.
80.00	Set basalt stone, 18 x 12 x 5 ins., 12 ins. in ground, for