

W. Bdy. T.4 S.,R.33 $\frac{1}{2}$ E.,W. M.

Chains	
	<p>to Secs. 27 & 34, marked T.4 S.,R.33$\frac{1}{2}$ E. on E. S.34 on S. and S.27 on N. faces, with 1 notch on S. and 5 notches on N. faces, from which A pine, 30 ins. diam.,brs. S.23°E., 71 lks. dist., marked T.4 S.,R.33$\frac{1}{2}$ E.,S.34,B.T. A tamarack, 20 ins. diam.,brs. N.75°E., 48 lks. dist., marked T.4 S.,R.33$\frac{1}{2}$ E.,S.27,B.T.</p> <p>Land; rolling hills. Soil; 2nd & 3rd rate. Heavily timbered with pine, fir & tamarack, except on S. 27.21 chs., open.</p>
	<p>N. on W. Bdy. Sec. 27. Var.19°E.</p>
14.81	<p>The Cor. to Secs. 25; 36, 30 & 31, which is a basalt stone, 18 x 10 x 5 ins., marked with 5 notches on N. and one notch on S. edges, from which A pine, 14 ins. diam.,brs. N.36°E., 68 lks. dist., marked T.4 S.,R.34 E.,S.30,B.T. A pine, 38 ins. diam.,brs. S.50°E., 47 lks. dist., marked T.4 S.,R.34 E.,S.31,B.T. A pine, 6 ins. diam.,brs. S.18°W., 56 lks. dist., marked T. 4 S., R.33 E.,S.36,B.T. A tamarack, 11 ins. diam., brs. N.63°W., 98 lks. dist., marked T.4 S.,R.33 E.,S.25,B.T.</p> <p>Destroyed marks referring to Secs. 30 & 31.</p>
43.00	Enter open glade, brs. E. & W.
54.90	The $\frac{1}{2}$ Sec. Cor.
58.40	Enter timber, brs. E. & W.
80.00	Set post, 4 ft. long, 4 ins. sq., 24 ins. in ground, for Cor. to Secs. 22 & 27, marked T.4 S.,R.33 $\frac{1}{2}$ E. on E., and S.27 on S. and S.22 on N. faces, with 4 notches on N., and 2 notches on S. edges, from which,