

Subdivisional Lines, T.4 S.,R.33 E.,W. M.

Chains	<p>A pine, 16 ins. diam., brs. N.28°W., 50 lks. dist., marked T.4 S.,R.33 E.,S.27,B.T.</p> <p>Land; surface rolling.</p> <p>Soil; 3rd, 2nd & 1st rate.</p> <p>Some scattering pine, tamarack & fir timber, thick in a few places.</p>
	<p>E. on random line bet. Secs. 26 & 35</p> <p style="text-align: right;">Var.19°45'E.</p>
1.00	Begin ascending.
11.00	On spur, extending S.W. † 100 ft.
19.00	A ravine, course S.W. Descent 60 ft.
40.00	Set temp. † Sec. Cor. Ascent 100 ft.
41.50	Ravine, course S. Descent 20 ft.
80.10	Ascent 30 ft. Intersected N. & S. line, 40 lks. N. of Cor. to Secs. 25, 26, 35 & 36.
	Thence I run
	N.89°43'W. on true line bet. Secs. 26 & 35.
	Var.20°35'E.
40.05	Set basalt stone, 16 x 12 x 8 ins., 11 ins. in ground, for † Sec. Cor., marked † on N. face, from which
	A pine, 8 ins. diam., brs. N.72°W., 68 lks. dist., marked † S.,B.T.
	A pine, 8 ins. diam., brs. S.36°W., 63 lks. dist., marked † S.,B.T.
80.10	The Cor. to Secs. 26, 27, 34 & 35.
	Land; surface rolling.
	Soil; 3rd & 2nd rate.
	Mostly heavy pine, tamarack & fir timber, with open glades.
	N. bet. Secs. 26 & 27.
	Var.19°45'E.
	Ascending W. slope of ridge.
40.00	Set basalt stone, 16 x 10 x 8 ins., 11 ins. in ground, for † Sec. Cor., marked † on W. face, from which
	A pine, 11 ins. diam., brs. S.80°E., 38 lks. dist.,