

Exterior Lines, T.5 S., R.33½ E., W. M.

Chains	<p>and 2 notches on W. edges; dug pits, 18 x 18 x 12 ins. in each Sec., 5½ ft. dist. and raised mound of earth 2 ft. high and 4½ ft. base alongside.</p> <p>Land; rolling.</p> <p>Soil; 2nd rate.</p> <p>Heavily timbered with pine & fir for 67 chs.</p>
	<p>S.89°59'E. on true line bet. Secs. 1 & 36.</p> <p style="text-align: right;">Var.19°40'E.</p>
40.00	<p>Set basalt stone, 12 x 10 x 8 ins., 8 ins. in ground, for ¼ Sec. Cor., marked ¼ on N. face; dug pits, 18 x 18 x 12 ins., E. & W. of stone, 5½ ft. dist.; raised mound of earth 1½ ft. high and 3½ ft. base alongside.</p>
80.00	<p>The Cor. to Tps. 4 & 5 S., Rs. 33½ & 34 E.</p> <p>Land; level.</p> <p>Soil; 2nd rate.</p> <p>Timber; scattering pine.</p> <p style="text-align: right;">Oct. 16, 1882.</p>
	<p>Exterior Lines, T.4 S., R.34 E., W. M. As surveyed by same U.S. Deputy, under Same Contract & date.</p>
	<p>From the Cor. to Tps. 4 & 5 S., Rs. 33½ & 34 E.,</p> <p>I run</p> <p>N. bet. Secs. 31 & 36.</p> <p style="text-align: right;">Var.20°E.</p>
32.00	<p>Wagon road, course N.E. & S.W. Enter heavy timber, course E. & W.</p>
40.00	<p>Set basalt stone, 13 x 12 x 8 ins., 8 ins. in ground, for ¼ Sec. Cor., from which,</p> <p style="padding-left: 40px;">A pine, 10 ins. diam., brs. N.52°E., 45 lks. dist., marked ¼ S., B.T.</p> <p style="padding-left: 40px;">A pine, 30 ins. diam., brs. N.40°W., 109 lks. dist., marked ¼ S., B.T.</p>
50.56	<p>Creek, 10 lks. wide, runs W.</p>
61.00	<p>House, about 10 chs. W., with field and other improvements</p>