

Subdivisional Lines, T.4 S., R.33½ E., W. M.

Chains	E. on random line bet. Secs. 25 & 36. Var. 20°E. Through timber.
18.00	Rancharee Creek, 6 lks. wide, runs S.
40.00	Set temp. ¼ Sec. Cor.
79.86	Intersected E. Bdy. of Tp., at Cor. to Secs. 25, 30, 31 & 36, which is a basalt stone, 13 x 10 x 7 ins., firmly set in ground, marked with 5 notches on N. and 1 notch on S. edges, from which, A pine, 10 ins. diam., brs. S. 36°W., 20 lks. dist., marked T.4 S., R.33½ E., S.36, B.T. A pine, 8 ins. diam., brs. N. 74°W., 10 lks. dist., marked T.4 S., R.33½ E., S.25, B.T. A pine, 10 ins. diam., brs. N. 66°E., 60 lks. dist., marked T.4 S., R.34 E., S.30, B.T. A pine, 15 ins. diam., brs. S. 28°E., 48 lks. dist., marked T.4 S., R.34 E., S.31, B.T. Thence I run W. on true line bet. Secs. 25 & 36, with same Vars.
39.93	Set basalt stone, 9 x 9 x 6 ins., 6 ins. in ground, for ¼ Sec. Cor., marked ¼ on N. face, from which, A pine, 27 ins. diam., brs. S. 65°E., 122 lks. dist., marked ¼ S., B.T. A pine, 24 ins. diam., brs. N. 10°W., 63 lks. dist., marked ¼ S., B.T.
79.86	The Cor. to Secs. 25, 26, 35 & 36. Land; gently rolling. Soil; 2nd rate. Heavily timbered with pine & fir. Dense undergrowth of pine & fir, the W. ½.
	N. bet. Secs. 25 & 26. Var. 20°E. Through timber.
25.00	Ravine, course E.
31.00	Enter Creek bottom, course N.W. & S.E.