

Subdivisional Lines, T.4 S., R.33 $\frac{1}{2}$ E., W. M.

Chains

- W. on true line bet. Secs. 24 & 25, with same Vars.
- 39.93 Set basalt stone, 18 x 8 x 6 ins., 12 ins. in ground, for $\frac{1}{4}$ Sec. Cor., marked $\frac{1}{4}$ on N. face, from which
- A pine, 12 ins. diam., brs. S.60°W., 14 lks. dist., marked $\frac{1}{4}$ S., B.T.
- A pine, 12 ins. diam., brs. N.50°E., 68 lks. dist., marked $\frac{1}{4}$ S., B.T.
- 79.87 The Cor. to Secs. 23, 24, 25 & 26.
- Land; gently rolling.
- Soil; 2nd rate.
- Heavily timbered with yellow pine & fir.
- Dense undergrowth of pine & fir.
-
- From the Cor. to Secs. 2, 3, 34 & 35, on S. Bdy. of Tp., which is a basalt stone, 14 x 13 x 5 ins., 9 ins. in ground, marked with 2 notches on E. and 1 notch on W. edges, and mound of stone, 2 ft. high and 4 $\frac{1}{2}$ ft. base alongside.
- Thence I run N. bet. Secs. 34 & 35.
- Var. 19°40'E.
- Over gently rolling ground.
- Scattering pine timber.
- 40.00 Set basalt stone, 12 x 10 x 5 ins., 9 ins. in ground, for $\frac{1}{4}$ Sec. Cor., marked $\frac{1}{4}$ on W. face. Raised mound of stone alongside.
- 50.00 Enter dense forest, course E. & W.
- 80.00 Set pine post, 4 ft. long, 4 ins. sq., 24 ins. in ground, for Cor. to Secs. 26, 27, 34 & 35, marked
- T.4 S., S.26 on N.E.
- R.33 $\frac{1}{2}$ E., S.35 on S.E.
- S.34 on S.W. and
- S.27 on N.W. faces, with
- 1 notch on S. and
- 2 notches on E. edges, from which
- A pine, 10 ins. diam., brs. N.24°E., 73 lks. dist., marked T.4 S., R.33 $\frac{1}{2}$ E., S.26, B.T.