

Subdivisional Lines, T.4 S., R.33 $\frac{1}{2}$ E., W. M.

Chains

- 23.60 Intersected W. Bdy. of Tp., 16 lks. N. of Cor. to Secs. 27 & 34, which is a post, 4 ins. sq., firmly set in ground, marked T.4 S., R.33 $\frac{1}{2}$ E., on E., S.34 on S. and S.27 on N. faces, with 1 notch on S. and 5 notches on N. faces, from which
- A pine, 30 ins. diam., brs. S.23°E., 71 lks. dist., marked T.4 S., R.33 $\frac{1}{2}$ E., S.34, B.T.
- A tamarack, 20 ins. diam., brs. N.75°E., 48 lks. dist. marked T.4 S., R.33 $\frac{1}{2}$ E., S.27, B.T.
- Thence I run N.89° 37' E. on true line bet. Secs. 27 & 34, with same Vars.
- 23.60 The Cor. to Secs. 26, 27, 34 & 35.
- Land; level.
- Soil; 2nd rate.
- Heavily timbered with pine, fir & tamarack.
- Good pine grass.
-
- N. bet. Secs. 26 & 27.
- Var.20°10'E.
- Ascending gently, through heavy timber.
- 8.00 A ravine, course S.E.
- 40.00 Set basalt stone, 15 x 12 x 4 ins., 10 ins. in ground, for $\frac{1}{4}$ Sec. Cor., marked $\frac{1}{4}$ on W. face, from which
- A pine, 30 ins. diam., brs. N.50°W., 22 lks. dist., marked $\frac{1}{4}$ S., B.T.
- A pine, 30 ins. diam., brs. N.84°E., 26 lks. dist., marked $\frac{1}{4}$ S., B.T.
- Gently descending.
- 80.00 Set basalt stone, 18 x 12 x 12 ins., 12 ins. in ground, for Cor. to Secs. 22, 23, 26 & 27, marked with 2 notches on S. & E. edges, from which,
- A pine, 8 ins. diam., brs. N.71°E., 14 lks. dist., marked T.4 S., R.33 $\frac{1}{2}$ E., S.23, B.T.
- A pine, 18 ins. diam., brs. S.50°E., 54 lks. dist., marked T.4 S., R.33 $\frac{1}{2}$ E., S.26, B.T.