

Exterior Lines, T.5 S.,R.34 E.,W. M.

Chains	W. on N. Bdy. of Sec. 5.	Var. 21°30'E.
12.40	Ravine, course N.W.	
40.00	Set post, 4 ft. long, 3 ins. sq., 24 ins. in ground, for $\frac{1}{4}$ Sec. Cor., marked $\frac{1}{4}$ S. on N. face, from which A pine, 8 ins. diam., brs. N.63°W., 12 lks. dist., marked $\frac{1}{4}$ S., B.T. A tamarack, 20 ins. diam., brs. S.30°W., 16 lks. dist., marked $\frac{1}{4}$ S., B.T.	
71.10	Ravine, course N.W.	
80.00	Set basalt stone, 18 x 15 x 8 ins., 12 ins. in ground, for Cor. to Secs. 5, 6, 31 & 32, marked with 5 notches on E. and 1 notch on W. edges, from which A pine, 6 ins. diam., brs. S.82°E., 172 lks. dist., marked T.5 S., R.34 E., S.5, B.T. A pine, 4 ins. diam., brs. N.68°E., 110 lks. dist., marked T.4 S., R.34 E., S.32, B.T. A pine, 12 ins. diam., brs. N.38°W., 127 lks. dist., marked T.4 S., R.34 E., S.31, B.T. A pine, 12 ins. diam., brs. S.70°W., 39 lks. dist., marked T.5 S., R.34 E., S.6, B.T.	
	Land; rolling.	
	Soil; 2nd rate.	
	Heavily timbered with pine & fir.	
	Undergrowth of fir, pine & willow.	
	W. on N. Bdy. of Sec. 6,	Var. 23°30' E.
28.00	Small ravine, course N.W.	
40.00	Set basalt stone, 20 x 12 x 8 ins., 15 ins. in ground, for $\frac{1}{4}$ Sec. Cor., marked $\frac{1}{4}$ on N. face, from which A pine, 36 ins. diam., brs. N.9°E., 150 lks. dist., marked $\frac{1}{4}$ S., B.T. A pine, 20 ins. diam., brs. S.28°W., 96 lks. dist., marked $\frac{1}{4}$ S., B.T.	
81.20	The Cor. to <del>Sp.</del> 4 & 5 S., Rs. 33 $\frac{1}{2}$ & 34 E.	