

## Subdivisional Lines &amp; Meanders, T 5 N R 27 E WM.

## Chains

- 40.00 Set  $\frac{1}{4}$  Sec. post; made mound and drove charred stake, as per instructions.
- 80.00 Set post, Cor. to Secs. 23, 24, 25 & 26; made mound and deposited charred stake, as per instructions.  
Surface; nearly flat with young sage, lupine, bunch grass, etc.

E. on random line bet. Secs. 24 & 25.

Var.  $21^{\circ}30'E$ .

- 40.00 Set temp.  $\frac{1}{4}$  Sec. post.
- 79.91 Intersect E. Bdy. of Tp., 19 lks. N. of Cor. to Secs. 24 and 25.  
N.  $89^{\circ}52'W$ . on true line bet. Secs. 24 & 25.
- 39.95 $\frac{1}{2}$  Set  $\frac{1}{4}$  Sec. post in mound, with charred stake, as per instructions.
- 79.91 To Cor. to Secs. 23, 24, 25 & 26.  
Soil & surface as in preceding mile.

N. bet. Secs. 23 & 24.

Var.  $21^{\circ}30'E$ .

- 40.00 Set  $\frac{1}{4}$  Sec. post; made mound; deposited charred stake, as per instructions.
- 74.00 Commence to descend Columbia Bluff.
- 80.00 Set post Cor. to Secs. 13, 14, 23 & 24; made mound and deposited charred stake, as per instructions.

Var.  $21^{\circ}15'E$ .

- E. on random, obliquely up the bluff bet. Secs. 13 & 24.
- 40.00 Set temp.  $\frac{1}{4}$  Sec. post.
- 80.00 Intersect E. Bdy. of Tp., 16 lks. N. of Sec. Cor.  
N.  $89^{\circ}53'W$ . on true line bet. Secs. 13 & 24.
- 40.00 Set  $\frac{1}{4}$  Sec. post; made mound and drove charred stake, as per instructions.
- Commence to descend.
- 80.00 To Cor. to Secs. 13, 14, 23 & 24.