

Subdivisional Lines & Meanders, T 5 N R 27 E W M.

Chains	
	Tuesday, Sept. 17, 1861
	N. bet. Secs. 33 & 34.
40.00	Set $\frac{1}{4}$ Sec. post; made mound and drove charred stake, as per instructions.
64.00	Old Emigrant & Wagon road, course N.W.
80.00	Set post Cor. to Secs. 27, 28, 33 & 34 ; made mound & drove charred stake, as per instructions.
<hr/>	
	E. on random bet. Secs. 27 & 34.
	Var. 21° E.
40.00	Set temp. $\frac{1}{4}$ Sec. post.
80.50	Intersect N. & S. line, 23 lks. N. of Cor. to Secs. 26, 27, 34 & 35.
	N. 89° 50' W. on true line bet. Secs. 27 & 34.
40.25	Set $\frac{1}{4}$ Sec. post; made mound & drove charred stake, as per instructions.
80.50	To Cor. of Secs. 27, 28, 33 & 34.
<hr/>	
	N. bet. Secs. 27 & 28.
	Var. 21° E.
	Begin to descend.
40.00	Set $\frac{1}{4}$ Sec. post; made mound and drove charred stake, as per instructions.
80.00	Set post Cor. to Secs. 21, 22, 27 & 28; made mound & drove charred stake, as per instructions.
<hr/>	
	E. on random line bet. Secs. 22 & 27.
	Var. 21° 20' E.
40.00	Set temp. $\frac{1}{4}$ Sec. post.
80.42	Intersect N. & S. line, 25 lks. N. of Cor. to Secs. 22, 23, 26 & 27.
	N. 89° 49' W. on true line bet. Secs. 22 & 27.
40.21	Set $\frac{1}{4}$ Sec. post; made mound & drove charred stake, as per instructions.