

Subdivisional Lines & Meanders, T 5 N R 27 E W M.

Chains	
80.42	To Cor. of Secs. 21, 22, 27 & 28.
	N. bet. Secs. 21 & 22.
	Var. 21°20'E.
40.00	Set $\frac{1}{4}$ Sec. post; made mound & drove charred stake, as per instructions.
80.00	Set post Cor. to Secs. 15, 16, 21 & 22; made mound & drove charred stake, as per instructions.
	E. on random bet. Secs. 15 & 22.
	Var. 21°20'E.
40.00	Set temp. $\frac{1}{4}$ Sec. post.
80.30	Intersect N. & S. line, 31 lks. N. of Cor. to Secs. 14, 15, 22 & 23.
	N. 89°47'W. on true line bet. Secs. 15 & 22.
40.15	Set $\frac{1}{4}$ Sec. post; made mound & drove charred stake, as per instructions.
80.30	To Cor. of Secs. 15, 16, 21 & 22.
	N. bet. Secs. 15 & 16.
	Var. 21°20'E.
28.50	Columbia Trail, course E. & W.
31.36	Set post; Meander Cor. to Secs. 15 & 16, on bank of Columbia River, about 12 ft. above & 5 chs. dist. from the water.
	Var. 21°E.
	Made mound & drove charred stake, as per instructions.
	Meanders of the Columbia River in Tp. 5 N., R 27 E.
40.00	Commencing on the Tp. line bet. Rs. 27 & 28 E. and Tp. 5 N. set $\frac{1}{4}$ Sec. post; made mound at the Meander Cor. bet. fractional Secs. 13 & 18.
	Thence down the left bank of S. side of River.
	Sept. 26, 1861.