

## Subdivisional Lines, T 5 N R 28 E W M.

Chains	Tuesday Sept. 10, 1861.
	N. bet. Secs. 25 & 26. Var. 20°30'E.
40.00	Set $\frac{1}{4}$ Sec. post; made mound; deposited charred stake, as per instructions. Leave the most of the sage and greasewood.
80.00	Set post Cor. to Secs. 23, 24, 25 & 26. The surface of this mile lies in sand dunes, coursing E. & W., from 2 to 5 chs. apart and from 6 to 12 ft. in height.
	E. on random line bet. Secs. 24 & 25. Var. 21°10'E.
40.00	Set temp. $\frac{1}{4}$ Sec. post.
79.80	Intersect N. & S. line, the E. Bdy. of Tp., 12 lks. N. of Sec. Cor. to Secs. 24 & 25. N. 89°55' W. on true line bet. Secs. 24 & 25.
39.90	Set $\frac{1}{4}$ Sec. post, in mound, with charred stake, as per instructions.
79.80	The Cor. to Secs. 23, 24, 25 & 26.
	N. bet. Secs. 23 & 24. Var. 21°10'E.
40.00	Set $\frac{1}{4}$ Sec. post, in mound, with charred stake, as per instructions. Enter rocky land.
72.00	Columbia Trail, course E. & W.
80.00	Set post Cor. to Secs. 13, 14, 23 & 24; made mound and drove charred stake, as per instructions.
	E. on random line bet. Secs. 13 & 24. Var. 20°45'E.
40.00	Set temp. $\frac{1}{4}$ Sec. post.
79.66	Intersect E. Bdy. of Tp., 40 lks. N. of Cor. to Secs. 13 & 14. N. 89°43' W. on true line bet. Secs. 13 & 24.