

Subdivisional Lines, T 5 N R 28 E W M.

Chains	
39.83	Set $\frac{1}{4}$ Sec. post, in mound, with charred stake, as per instructions.
79.66	To Cor. of Secs. 13, 14, 23 & 24. Surface; flat and rocky.
N. bet. Secs. 13 & 14. Var. 21°45'E.	
40.00	Set $\frac{1}{4}$ Sec. post, in mound, with charred stake, as per instructions.
80.00	Set post Cor. to Secs. 11, 12, 13 & 14; made mound; drove charred stake, as per instructions. Surface; flat & rocky. Between the rocks, sand, sage and bunch grass.
E. on random line bet. Secs. 12 & 13. Var. 20°20'E.	
40.00	Set temp. $\frac{1}{4}$ Sec. post.
79.62	Intersect E. Bdy. of Tp., 28 lks. N. of Cor. to Secs. 12 & 13. N. 89°48'W. on true line bet. Secs. 12 & 13.
39.81	Set $\frac{1}{4}$ Sec. post, in mound, with charred stake, as per instructions.
79.62	To Cor. of Secs. 11, 12, 13, & 14.
N. bet. Secs. 11 & 12. Var. 20°20'E.	
40.00	Set $\frac{1}{4}$ Sec. post, in mound, with charred stake, as per instructions.
45.20	Edge of perpendicular bluff over looking the Columbia River.
55.00	Set Meander. post Cor. to Secs. 11 & 12, on bank of River, 30 ft. above water, and made mound of rock, depositing charred stake. Var. 19°40'E.
Surface of this mile is generally flat; but broken by rocks	