

Subdivisional Lines, T 5 N R 28 E W M.

Chains.	
40.37½	Set post, ¼ Sec. Cor., in mound, with charred stake, as per instructions.
80.75	To Cor. to Secs. 14, 15, 10 & 11.
N. bet. Secs. 10 & 11.	
Var.	
18.00	Begin to descend Columbia bluff.
40.00	At foot of bluff,
	Set ¼ Sec. post, in mound, with charred stake, as per instructions.
55.10	Set Meander Cor. post Cor. to Secs. 10 & 11; made mound ; drove charred stake, as per instructions.
Var. 20°45'E.	
Thursday, Sept. 12, 1861.	
Commence on the Standard Parallel, at the Cor. of Secs. 33 and 34, on top of rocky spine or bluff, E. of Umatilla River and elevated 75 or 100 ft. above River.	
Thence	
N. bet. Secs. 33 & 34.	
Var. 20°30'E.	
40.00	Set ¼ Sec. post, in mound, with charred stake, as per instructions.
80.00	Set post Cor. to Secs. 33, 34, 27 & 28; made mound of rock and deposited charred stake, as per instructions, on E. side of rocky point.
E. on random line bet. Secs. 27 & 34.	
Var. 18°30'E.	
40.00	Set temp. ¼ Sec. post.
80.27	Intersect N. & S. line, 5 lks. N. of Cor. to Secs. 27 & 34, 26 & 35.
	N. 89°58' W. on true line bet. Secs. 27 & 34.
Commence descending.	
40.13½	Set ¼ Sec. Cor. post; made mound & deposited charred stake