

## Subdivisional Lines, T 5 N R 28 E W M.

Chains	as per instructions.
80.27	To Cor. to Secs. 27, 28, 33 & 34.
	N. bet. Secs. 27 & 28.
	Var. 18°30'E.
15.00	Bottom of hollow.
35.00	Top of knob.
40.00	Set $\frac{1}{4}$ Sec. Cor. post; made mound, with charred stake, as per instructions.
43.50	Perpendicular ridge of rock.
80.00	Set post Cor. to Secs. 21, 22, 27 & 28.
	E. on random bet. Secs. 22 & 27.
	Var. 20°40'E.
40.00	Set temp. $\frac{1}{4}$ Sec. post.
80.33	Intersect N. & S. line, 11 lks. S. of Cor. to Secs. 22, 23, 26 & 27.
	S. 89°55'W. on true line bet. Secs. 22 & 27.
40.16 $\frac{1}{2}$	Set $\frac{1}{4}$ Sec. Cor. post; made mound; drove stake, as per instructions.
80.33	To Cor. of Secs. 21, 22, 27 & 28.
	N. bet. Secs. 21 & 22.
	Var. 20°40'E.
40.00	Set $\frac{1}{4}$ Sec. post; made mound; drove charred stake, as per instructions.
80.00	Set post Cor. to Secs. 15, 16, 21 & 22; made mound and drove charred stake, as per instructions.
	Surface; undulating.
	Soil; sand, with sage, greasewood and bunch grass.
	E. on random line bet. Secs. 15 & 22.
	Var. 20°15'E.
40.00	Set temp. $\frac{1}{4}$ Sec. post.