

## Subdivisional Lines, T 5 N R 28 E W M.

Chains	21 & 22.
	N.89°47'W. on true line bet. Secs. 16 & 21.
25.80	N. point of rocky ridge.
40.40	Set $\frac{1}{4}$ Sec. post; made mound and drove charred stake, as per instructions.
78.80	Umatilla Road.
80.00	Umatilla River.
80.80	To Cor. of Secs. 16, 17, 20 & 21.
<hr/>	
	N. bet. Secs. 16 & 17.
	Var.21°15'E.
4.00	Bank of river.
5.00	Umatilla road, N.20°W.
28.00	Top of bluff.
30.50	Commence to descend.
37.00	Foot of bluff and Columbia Trail, course N.E.
40.00	Set $\frac{1}{4}$ Sec. post; made mound and drove charred stake, as per instructions.
80.00	Set post Cor. to Secs. 8, 9, 16 & 17; made mound and deposited charred stake, as per instructions.
<hr/>	
	E. on random line bet. Secs. 9 & 16.
	Var.20°30'E.
40.00	Set temp. $\frac{1}{4}$ Sec. post.
80.50	Intersect N. & S. line, 37 lks. N. of Cor. to Secs. 9, 10, 15 & 16.
	N.89°44'W. on true line bet. Secs. 9 & 16.
40.25	Set $\frac{1}{4}$ Sec. post; made mound and drove stake as per instructions.
80.50	To Cor. of Secs. 8, 9, 16 & 17.
<hr/>	
	N. bet. Secs. 8 & 9.
	Var.20°30'E.
17.50	Set Meander Cor. to Secs. 8 & 9, on bank of Columbia River about 1.00 from the water and opposite a low, gravelly