

Subdivisional Lines, T 5 N R 28 E W M.

Chains	Var.21°25'E.
	N. bet. Secs. 29 & 30.
40.00	Set $\frac{1}{4}$ Sec. post in mound, with charred stake, as per instructions.
62.00	Commence to descend.
80.00	Set post Cor. to Secs. 19, 20, 29 & 30; made mound and drove charred stake, as per instructions. Soil; less sandy, fine bunch grass & less sage.
	E. on random line bet. Secs. 20 & 29.
	Var.21°6'E.
40.00	Set temp. $\frac{1}{4}$ Sec. post.
80.08	Intersect N. & S. line, 30 lks. N. of Sec. Cor. W. 89°47'W. on true line bet. Secs. 20 & 29. Commence ascending.
40.04	Set $\frac{1}{4}$ Sec. post; made mound & drove charred stake, as per instructions.
80.08	To Cor. of Secs. 19, 20, 29 & 30.
	N. bet. Secs. 19 & 20.
	Var.21°6'E.
	Descend from Cor.
40.00	Set $\frac{1}{4}$ Sec. Cor. post; made mound and drove charred stake, etc.
60.00	Commence to ascend.
76.00	Top of bluff.
80.00	Set post Cor. to Secs. 17, 18, 19 & 20; made mound and deposited charred stake, as per instructions.
	E. on random line bet. Secs. 17 & 20.
	Var.21°E.
40.00	Set temp. $\frac{1}{4}$ Sec. post.
80.30	Intersect N. & S. line at Sec. Cor. in river (Umatilla) W. on true line bet. Secs. 17 & 20.
.12	Shore of island, edge of water.