

Ext. Bdys. T.5 N., R.30 E., W.M.

Chains	N. on line bet. Secs. 18, R.30 E. & Sec. 13, R.29 E.
31.50	Descend rocky bluff, bank about 25 ft. in height, E. & W.
40.00	Set charred stake, with mound, trench & pits, as per instructions, for $\frac{1}{4}$ Sec. Cor.
80.00	Set charred stake, with mound, trench & pits, as per instructions, for Cor. to Secs. 7 & 18, R.30 E., & Secs. 12 & 13, R.29 E.
	Var. 19°E.
	This mile, sandy and rough. Some sage brush.
	N. on line bet. Secs. 7, R.30 E. & Sec. 12, R.29 E.
8.00	Trail, N.70°E.
8.18	Edge of slough, bluff bank about 40 ft. in height.
	Set charred stake, with mound, trench & pits, for Meander Cor.
	Set up flag for object to triangulate to, from the N. side of slough.
	Regain the line on the N. bank of slough, offset 2.00 chs. due W., object on S. bank brs. S.12°24'E., making the width of slough 9.14 chs.
17.32	To N. bank of slough.
	Set Meander post, with mound, trench & pits, as per instructions.
40.00	Set charred stake, with mound, trench & pits, as per instructions, for $\frac{1}{4}$ Sec. Cor.
67.00	S. bank of main channel of the Columbia River.
	Set charred stake, with mound, trench & pits, as per instructions, for Meander Cor. bet. fractional Secs. 7 & 12.
	Var. 19°45'E.
	On this line, the land is rough, broken and sandy to the S. side of slough. After crossing the slough, the land is level and produces a large crop of grass, wild sun flowers and other vegetation.
	Soil; sandy, apparently not subject to inundation.