

## General Description, T 5 N R 29 E W M.

The greater part of this Township is broken and rocky, and excepting a small part in the S. E. Cor. is mostly occupied with rocks, sand, sage, greasewood & cactus, to the exclusion of bunch grass, that, which alone prevents or redeems it from the appellation of "A Desert".

Field Notes  
of  
Subdivision of Section 32.  
and  
Survey of lots in said section in  
T 5 N R 29 E , of Willamette Merid-  
ian, Oregon.

Executed by E. T. Erickson, Assistant  
Engineer, U. S. R. S., under authority  
of Departmental Instructions of  
October 24, 1906.

I begin at the Standard Cor. bet. Secs. 31 & 32, being the SW. Cor. of Secs. 32, T 5 N R 29 E of W.M., Oregon, and being found in place on the 1st Standard Parallel N., & marked by a hollow iron post, 3 ins. diam., projecting 2 ins. above ground.

The SE. Cor. of said Sec. 32, was also found in place, thus definitely marking the line of the 1st Standard Parallel North.

This Parallel being an established line of controlling importance in an accepted official survey, was used for horizontal control and deflections turned therefrom, from the basis of all bearings of lines determined by this survey.

All Cors. &  $\frac{1}{4}$  Cors. of Secs. 32, T 5 N R 29 E W M., were found in place excepting the  $\frac{1}{4}$  Cor. on S. side of said Sec. 32. This  $\frac{1}{4}$  Cor. not being found after diligent search was re-established as follows: