

Subdivision Sec.32, T 5 N R 29 E W M., Oregon.

Chains	
40.28	<p>1 in. diam., 24 ins. long, set 22 ins. in ground, $\frac{1}{4}$ Cor. on S. line, said Sec.32, being the SE Cor. of SW$\frac{1}{4}$ of said Sec.32, marked as heretofore noted. From SE Cor. of SW$\frac{1}{4}$ of said Sec.32, just described, being the $\frac{1}{4}$ Cor. on S line of said Sec.32, I run on true line N.0°07'W., (the distance from the $\frac{1}{4}$ Cor. on S. line to the center $\frac{1}{4}$Cor.of said Sec.32, having been previously measured in this survey and heretofore noted as 39.87 chs.)</p>
19.94	<p>Establish 1/16 Cor. on E. line & equidistant bet. the SE & NE Cors. of SW$\frac{1}{4}$ of said Sec.32, and mark same by iron post, 1 in. diam., 24 ins. long, set 22 ins. in ground.</p>
39.87	<p>Intersect center $\frac{1}{4}$ Cor. of said Sec.32, being NE Cor. of the SW$\frac{1}{4}$ of said Sec.32, marked as heretofore noted. The 1/16 Cors. on all 4 sides of the SW$\frac{1}{4}$ of said Sec.32, being now established, I proceed further with the subdivision, first by running the N.& S. center line of said $\frac{1}{4}$ Sec. From the 1/16 Cor. on S. line of SW$\frac{1}{4}$ of said Sec.32, previously established by this survey & marked as heretofore noted, I run on true line N.0°07' W.</p>
20.00	<p>Set stake for temp. 1/16 Cor. at center of $\frac{1}{4}$ Sec.</p>
39.92	<p>Intersect 1/16 Cor. on N. line of SW$\frac{1}{4}$ of said Sec.32, previously established by this survey & marked as heretofore noted, retracing on true line S.0°07'E.</p>
19.92	<p>Set temp. 1/16 Cor. for center of $\frac{1}{4}$ Sec., to be checked by intersection with the E. & W. center line of said $\frac{1}{4}$ Sec. which I now proceed to run.</p>
	<p>From the 1/16 Cor. on E. line of SW$\frac{1}{4}$, said Sec.32, previously established by this survey & marked as heretofore noted, I run on true line N.89°55'W.</p>
20.14	<p>Intersect temp. 1/16 Cor., set on N & S center line of SW$\frac{1}{4}$ of said Sec. 32.</p>
40.28	<p>Intersect 1/16 Cor. on W.line of SW$\frac{1}{4}$ of said Sec.32, previously established by this survey & marked as heretofore noted. Retracing I run on true line S 89°55'E.</p>