

Subdivisional Lines, T 5 N R 30 E W M.

Chains	S.89°50' W. on true line bet. Secs. 25 & 36.
7.15	Indian Trail, N.45°E.
39.64	Set charred stake, with mound, trench & pits, as per instructions, for $\frac{1}{4}$ Sec. Cor.
79.28	Cor. to Secs. 25, 26, 35 & 36. Soil; 2nd rate.
	N. on line bet. Secs. 25 & 26.
37.50	Begin to descend deep ravine.
40.00	Set charred stake, with mound, trench & pits, as per instructions, for $\frac{1}{4}$ Sec. Cor.
47.60	Indian Trail, W.
48.00	Bottom of ravine about 250 ft. deep, course W.
55.50	Top of hill.
80.00	Set charred stake, with mound, trench & pits, for Cor. to Secs. 23, 24, 25 & 26, as per instructions. Land; broken. Soil; 3rd rate. Var. 19°30'E.
	E. on random bet. Secs. 24 & 25.
40.00	Set temp. $\frac{1}{4}$ Sec. Cor.
79.84	Intersect Tp. line, 13 lks. N. of post Cor. to Secs. 24 & 25.
	N.89°55'W. on true line bet. Secs. 24 & 25.
5.10	Indian trail, course N.
39.92	Set charred stake, with mound, trench & pits, as per instructions, for $\frac{1}{4}$ Sec. Cor.
79.84	Cor. to Secs. 23, 24, 25 & 26.
	N. on line bet. Secs. 23 & 24.
40.00	Set charred stake, with mound, trench & pits, as per instructions, for $\frac{1}{4}$ Sec. Cor.
80.00	Set charred stake, with mound, trench & pits, as per instructions, for Cor. to Secs. 13, 14, 23 & 24. Soil; 2nd rate. Var. 19°45'E.