

Subdivisional Lines, T 5 N R 30 E W M.

Chains	
80.00	Set charred stake, with mound, trench & pits, as per instructions for Cor. to Secs. 1, 2, 11 & 12. Var. 20°E. Soil; 2nd rate.
	E. on random bet. Secs. 1, & 12.
40.00	Set temp. $\frac{1}{4}$ Sec. Cor.
78.50	Intersect Tp. line, 50 lks. N. of post Cor. to Secs. 1 & 12. N. 89°39' W. on true line bet. Secs. 1 & 12.
39.25	Set charred stake, with mound, trench & pits, for Cor. to Secs. 1, 2, 11 & 12, as per instructions. Soil; 2nd rate.
	Closing Cor. in sight, run N. 1°21' W. on true line bet. Secs. 1 & 2.
25.00	Begin to descend hill.
40.00	Set charred stake, with mound, trench & pits, as per instructions, for $\frac{1}{4}$ Sec. Cor.
79.50	Intersect Tp. line at post Cor. to Secs. 1 & 2, T 5 & 35 and 36, T 6 N R 30 E. Soil; somewhat sandy, 2nd rate.
	N. on line bet. Secs. 34 & 35. Var. 20°15'E.
40.00	Set charred stake, with mound, trench & pits, as per instructions, for $\frac{1}{4}$ Sec. Cor.
80.00	Set charred stake, with mound, trench & pits, as per instructions, for Cor. to Secs. 26, 27, 34 & 35. Var. 20°06'E. Soil; 2nd rate.
	Sept. 20.
	E. on random bet. Secs. 26 & 35.
40.00	Set temp. $\frac{1}{4}$ Sec. Cor.