

Subdivisional Lines, T 5 N R 30 E W M.

Chains	
	E. on random bet. Secs. 14 & 23.
40.00	Set temp. $\frac{1}{4}$ Sec. Cor.
80.24	Intersect Sec. line, 60 lks. N. of Cor. to Secs. 13, 14, 23 & 24.
	N.89°54'W. on true line bet. Secs. 14 & 23.
40.12	Set charred stake, with mound, trench & pits, as per instructions, for $\frac{1}{4}$ Sec. Cor.
80.24	Cor. to Secs. 14, 15, 22 & 23. Soil; 2nd rate.
	N. on line bet. Secs. 14 & 15.
40.00	Set charred stake, with mound, trench & pits, as per instructions, for $\frac{1}{4}$ Sec. Cor.
80.00	Set charred stake, with mound, trench & pits, as per instructions, for Cor. to Secs. 10, 11, 14 & 15. Var.20°06'E. Soil; 2nd rate.
	E. on random line bet. Secs. 11 & 14.
40.00	Set temp. $\frac{1}{4}$ Sec. Cor.
80.10	Intersect Sec. line, 60 lks. N. of Cor. to Secs. 11, 12, 13 and 14.
	N.89°34'W. on true line bet. Secs. 11 & 14.
18.50	Indian Trail, N.45°W.
40.05	Set charred stake, with mound, trench & pits, as per instructions, for $\frac{1}{4}$ Sec. Cor.
80.10	Cor. to Secs. 10, 11, 14 & 15. Soil; 2nd rate.
	N. on line bet. Secs. 10 & 11.
40.00	Set charred stake, with mound, trench & pits, as per instructions, for $\frac{1}{4}$ Sec. Cor.
54.00	Begin to descend towards the Columbia River.
80.00	Set charred stake, with mound, trench & pits, as per instructions, for Cor. to Secs. 2, 3, 10 & 11. Some rocks, Soil; 3rd rate. Var.19°45'E.