

Subdivisional Lines, T 5 N R 30 E W M.

Chains	E. on random bet. Secs. 2 & 11.
40.00	Set temp. $\frac{1}{4}$ Sec. Cor.
80.00	Intersect Sec. line, 70 lks. N. of Cor. to Secs. 1, 2, 11 & 12 N. $89^{\circ}30'W.$ on true line bet. Secs. 2 & 11.
10.00	Begin to descend hill towards the river.
40.00	Set charred stake, with mound, trench & pits, as per instructions, for $\frac{1}{4}$ Sec. Cor.
64.50	Indian Trail, N. $40^{\circ}W.$
80.00	Cor. to Secs. 2, 3, 10 & 11. Soil; somewhat sandy, 3rd rate.
<hr/>	
	Closing Cor. being in sight, run N. $1^{\circ}21'W.$ on true line bet. Secs. 2 & 3.
40.00	Set charred stake, with mound, trench & pits, as per instructions, for $\frac{1}{4}$ Sec. Cor.
51.00	Indian Trail, N. $20^{\circ}W.$
62.00	Descend rocky bluff. (Variation at this point $23^{\circ}50'E.$)
79.50	Intersect Tp. line at post Cor. to Secs. 2 & 3. Land; poor.
<hr/>	
	Sept. 21, 1861
	N. on line bet. Secs. 33 & 34. Var. $20^{\circ}E.$
40.00	Set charred stake, with mound, trench & pits, as per instructions, for $\frac{1}{4}$ Sec. Cor.
80.00	Set charred stake, with mound, trench & pits, as per instructions, for Cor. to Secs. 27, 28, 33 & 34. Var. $20^{\circ}30'E.$
	Soil; 2nd rate.
<hr/>	
	E. on random line bet. Secs. 27, & 34.
40.00	Set temp. $\frac{1}{4}$ Sec. Cor.
79.96	Intersect line, 19 lks. N. of Cor. to Secs. 26, 27, 34 & 35. N. $89^{\circ}56'W.$ on true line bet. Secs. 27 & 34.
39.98	Set charred stake, with mound, trench & pits, as per in-