

Subdivisional Lines, T 5 N R 30 E W M.

Chains	structions, for $\frac{1}{4}$ Sec. Cor.
79.96	Cor. to Secs. 27, 28, 33 & 34.
	N. on line bet. Secs. 27 & 28.
12.00	Begin to descend into ravine.
16.60	Bottom of ravine, about 100 ft. deep.
26.00	Top of hill.
40.00	Set charred stake, with mound, trench & pits, as per instructions, for $\frac{1}{4}$ Sec. Cor.
80.00	Set charred stake, with mound, trench & pits, as per instructions, for Cor. to Secs. 21, 22, 27 & 28.
	Var. $20^{\circ}30'E$.
	Soil; 3rd rate.
	E. on random line bet. Secs. 22 & 27.
40.00	Set temp. $\frac{1}{4}$ Sec. Cor.
80.10	Intersect Sec. line, 36 lks. N. of Cor. to Secs. 22, 23, 26 & 27.
	N. $89^{\circ}45'W$. on true line bet. Secs. 22 & 27.
40.05	Set charred stake, with mound, trench & pits, as per instructions, for $\frac{1}{4}$ Sec. Cor.
80.10	Cor. of Secs. 21, 22, 27 & 28.
	Soil; 2nd rate.
	N. on line bet. Secs. 21 & 22.
40.00	Set charred stake, with mound, trench & pits, for $\frac{1}{4}$ Sec. Cor., as per instructions.
80.00	Set charred stake, with mound, trench & pits, for Cor. to Secs. 15, 16, 21 & 22, as per instructions.
	Var. $19^{\circ}48'E$.
	Soil; 2nd rate.
	E. on random bet. Secs. 15 & 22.
40.00	Set temp. $\frac{1}{4}$ Sec. Cor.
80.00	Intersect Sec. line, 60 lks. N. of Cor. to Secs. 14, 15,