

Subdivisional Lines, T 5 N R 30 E W M.

Chains

Closing Cor. being in sight, run

S.89°55'E. on true line bet. Secs. 3 & 10.

40.06 Set charred stake, with mound, trench & pits, as per instructions, for $\frac{1}{4}$ Sec. Cor.

80.12 Cor. to Secs. 2, 3, 10 & 11.

N.50'W. on true line bet. Secs. 3 & 4.

10.50 Begin to descend steep hill.

37.50 Indian Trail, E. & W.

40.00 Set charred stake, with mound, trench & pits, as per instructions, for $\frac{1}{4}$ Sec. Cor.

47.70 Ascend perpendicular bluff. Rocks about 100 ft. high.

65.10 Descend perpendicular rocky bluffs about 50 ft. high.

At this point Var. 29°E

74.00 Descend steep rocky bluff about 30 ft. high.

76.60 Descend rocky bluff about 25 ft. high.

79.40 Descend rocky bluff about 50 ft. high.

79.60 Intersect Tp. line at post Cor. to Secs. 3 & 4.

Sept. 22, 1861.

N. on line bet. Secs. 32 & 33.

Var.20°E.

40.00 Set charred stake, with mound, trench & pits, as per instructions, for $\frac{1}{4}$ Sec. Cor.

59.00 Begin to descend, into ravine.

67.00 Bottom of ravine, 100 ft. deep, course W.

76.50 Top of hill.

80.00 Set charred stake, with mound, trench & pits, as per instructions, for Cor. to Secs. 28, 29, 32 & 33.

Var.20°E.

Land; hilly & rocky.

Soil; 3rd rate.

Closing Cor. being in sight, run

E. on true line bet. Secs. 28 & 33.