

## Subdivisional Lines, T 5 N R 30 E W M.

Chains	E. on random bet. Secs. 29 & 32.
40.00	Set temp. $\frac{1}{4}$ Sec. Cor.
79.80	Intersect Sec. line, 14 lks. S. of Cor. to Secs. 28, 29, 32 & 33.
	S.89°34'W. on true line bet. Secs. 29 & 32.
39.90	Set charred stake, with mound, trench & pits, as per instructions, for $\frac{1}{4}$ Sec. Cor.
79.80	Cor. to Secs. 29, 30, 31 & 32. Soil; 2nd rate.
	W. on random bet. Secs. 30 & 31.
40.00	Set temp. $\frac{1}{4}$ Sec. Cor.
79.94	Intersect Tp. line, 50 lks. N. of Cor. to Secs. 30 & 31.
	N.89°39'E. on true line bet. Secs. 30 & 31.
39.94	Set charred stake, with mound, trench & pits, as per instructions, for $\frac{1}{4}$ Sec. Cor.
79.94	Cor. to Secs. 29, 30, 31 & 32. Soil; 2nd rate.
	N. on line bet. Secs. 29 & 30.
40.00	Set charred stake, with mound, trench & pits, as per instructions, for $\frac{1}{4}$ Sec. Cor.
80.00	Set charred stake, with mound, trench & pits, as per instructions for Cor. to Secs. 19, 20, 29 & 30. Var.20°18'E.
	Soil; 2nd rate.
	E. on random line bet. Secs. 20 & 29.
40.00	Set temp. $\frac{1}{4}$ Sec. Cor.
79.78	Intersect Sec. line, 32 lks. N. of post Cor. to Secs. 20, 21, 28 & 29.
	N.89°45'W. on true line bet. Secs. 20 & 29.
39.89	Set charred stake, with mound, trench & pits, as per instructions, for $\frac{1}{4}$ Sec. Cor.