

Subdivisional Lines, T 5 N R 30 E W M.

Chains	
40.00	Set charred stake, with mound, trench & pits, for $\frac{1}{4}$ Sec. Cor.
80.00	Cor. to Secs. 17, 18, 19 & 20. Soil; 3rd rate.
	N. on line bet. Secs. 17 & 18.
40.00	Set charred stake, with mound, trench & pits, as per instructions, for $\frac{1}{4}$ Sec. Cor.
59.40	Perpendicular bluff rocks, about 12 ft. high, S.40°W.
80.00	Set charred stake, with mound, trench & pits, as per instructions, for Cor. to Secs. 7, 8, 17 & 18. Var.20°30'E.
	E. on random line bet. Secs. 8 & 17.
40.00	Set temp. $\frac{1}{4}$ Sec. Cor.
80.24	Intersect Sec. line, 39 lks. N. of post Cor. to Secs. 8, 9, 16 & 17. N.89°43'W. on true line bet. Secs. 8 & 17.
4.60	Descend rocky bluff, N. & S.
40.12	Set charred stake, with mound, trench & pits, as per instructions, for $\frac{1}{4}$ Sec. Cor.
41.50	Indian Trail, N.
80.24	Cor. to Secs. 7, 8, 17 & 18.
	W. on random bet. Secs. 7 & 18.
40.00	Set temp. $\frac{1}{4}$ Sec. Cor.
80.00	Intersect Tp. line, 30 lks. N. of Cor. to Secs. 7 & 18. N.89°47'E. on true line bet. Secs. 7 & 18.
40.00	Set charred stake, with mound, trench & pits, as per instructions, for $\frac{1}{4}$ Sec. Cor.
80.00	Cor. to Secs. 7, 8, 17 & 18.
	N. on line bet. Secs. 7 & 8.
27.00	Descend steep bluff.
40.00	Set charred stake, with mound, trench & pits, as per in-