

Subdivisional Lines, T 5 N R 30 E W M.

Chains.

N. on line bet. fractional Secs. 5 & 6.
 19.82 S. bank of Columbia River.
 Set charred stake, with mound, trench & pits, as per instructions, for Meander Cor. bet. fractional Secs. 5 & 6.
 Var. 19°E.

Meanders of left bank of Columbia River, T 5 N R 30 E W M. As surveyed by same U.S. Deputy Surveyor, Under same Contract & date.

Beginning at the point where the N. line of Tp. intersects the river bank, being the ~~Cor. to~~ fractional Secs. 4, T 5 and Sec. 33, T 6 N.

Thence run down the stream with the meanders thereof in Sec. 4

S. 57 $\frac{3}{4}$ °W. ' 89.14 chs. ' To Cor. fractional Secs. 4 & 5, thence in Sec. 5.

S. 57 $\frac{3}{4}$ °W. ' 2.86 chs. ' Head of dry slough, course S. 50°W., 7 chs. wide.

S. 86 $\frac{1}{2}$ °W. 59.45 chs.

S. 70°W. 10.90 "

S. 76 $\frac{1}{8}$ °W. 7.70 " ' To Cor. of fractional Secs. 5 & 6, thence in Sec. 6.

N. 86°W. 9.82 chs.

S. 70°W. 17.58 "

S. 61°W. 15.08 "

S. 66 $\frac{1}{4}$ °W. 16.35 " To Cor. of fractional Secs. 6 & 7, thence in Sec. 7.

S. 66 $\frac{1}{4}$ °W. 23.82 chs.

S. 49°W. 5.47 " Intersect Tp. line at post Cor. to fractional Secs. 7, R. 30 & 12, R. 29.