

Resurvey S. Bdy., T 6 N R 30 E W M.

Chains	<p>under stone; dig pits, 18 x 18 x 12 ins. E. & W. of stone, 3 ft. dist. and raise mound of earth, 3½ ft. base, 1½ ft. high, N. of Cor. No trace of old Cor. to be found.</p> <p>Ascend from ¼ Sec. Cor.</p> <p>42.80 Ascend rimrock, 30 ft. high, brs. N.20°E and S. 20 ° W. Thence over flat table land.</p> <p>62.34 Descend rimrock, 50 ft. high, hrs.N.60°E. & S.60 ° W.</p> <p>73.00 Wire fence brs. N. & S.</p> <p>73.94 Descend rock bluff, 60 ft. high, brs. N.E. & S.W.</p> <p>80.00 Set basalt stone, 30 x 24 x 18 ins., 22 ins. in ground, for Cor. of Secs. 3, 4, 33 & 34, mkd. with 3 notches on E. & W. edges; dig pits, 18 x 18 x 12 ins., in each Sec., 5½ ft. dist. and raise mound of earth, 4 ft. base 2 ft. high, N. of Cor. (the ground on W. of Cor. being too steep to hold a mound). No trace of old Cor.</p> <p>Land; rolling & mountainous. Last 20 chs. very broken. Soil; light, sandy & volcanic ash, 1st & 4th rates. No timber.</p> <p>Undergrowth; sage & greasewood with a good growth of bunch grass.</p>
	<p>W. bet. Secs. 4 & 33.</p> <p>Descending.</p> <p>1.80 Brink of irregular basalt bluffs, facing N.W.</p> <p>4.30 At this point, I make diligent search, but fail to find any trace of the old Meander Cor. of Secs. 4 & 33, set by Deputy Payne in 1861.</p> <p>6.45 Foot of bluffs, in railroad cut, 360 ft. below Sec. Cor. Cut a cross in face of bluff on line.</p> <p>7.48 Southeasterly, the mean high water line on left bank of the Columbia River. The point for the Meander Cor. falls on a basalt boulder, 48 x 36 x 18 ins., in place, on which I cut a cross, at exact point for the Meander Cor. of fractional Secs. 4 & 33, mkd. MC on W., R 30 E on E., T 6 N S 33 on N. and T 5 N S 4 on S. faces & raise</p>