

Exterior Lines, T 5 N R 31 E W M.  
 As surveyed by William H. Odell, U.S. Deputy Surveyor,  
 Under Contract No. 110,  
 Dated Feby. 7, 1865.

## Chains

N. on E. Bdy. of Sec. 36, T 5 N R 31 E.

Var. 20° E.

40.00 Set  $\frac{1}{4}$  Sec. post on hillside, sloping to the W.; drove charred stake; dug pits & raised mound, as per instructions.

80.00 Set post Cor. to Secs. 25, 36, 31 & 30, on side of ravine, foot of hill, 60 ft. high; drove charred stake; dug pits and raised mound, as per instructions.

Land; broken. Grass good. Soil; 2nd rate.

N. on E. Bdy. of Sec. 25, T 5 N R 31 E.

40.00 Set  $\frac{1}{4}$  Sec. post on W. side of ravine, sloping SE.; drove charred stake; dug pits; raised mound, as per instructions.

80.00 Set post Cor. to Secs. 24, 25, 19 & 30, head of gully on E. side; drove charred stake; dug pits & raised mound, etc. as per instructions. Soil; 2nd rate.

Land; broken. Soil; 2nd rate. Good grass.

N. on E. Bdy. of Sec. 24, T 5 N R 31 E.

Var. 19° 45' E.

40.00 Set  $\frac{1}{4}$  Sec. post. Land sloping to the SW. Drove charred stake dug pits; raised mound as per instructions.

80.00 Set post Cor. to Secs. 13, 24, 18 & 19, on brink of hill, E. side of gully, course S W. Drove charred stake; dug pits & raised mound, as per instructions.

Land; broken. Grass good. Soil; 2nd rate.

N. on E. Bdy. of Sec. 13, T 5 N R 31 E.

Var. 21° E.

40.00 Set  $\frac{1}{4}$  Sec. post, head of ravine, course W. Drove charred stake; dug pits & raised mound, as per instructions.

80.00 Set post Cor. for Secs. 12, 13, 18 & 7, on E. side of ravine, course W. Drove charred stake; dug pits & raised mound, as per instructions.

Land; broken. Grass good. Soil; 2nd rate.

N. on E. Bdy. of Sec. 12, T 5 N R 31 E.

Var. 21° E.