

Subdivisional Lines, T 5 N R 31 E W M.

Chains.	N. bet. Secs. 15 & 16.
	Var. 21°E.
40.00	Drove charred stake; raised mound of earth, with pits, etc., as per instructions, for $\frac{1}{4}$ Sec. Cor.
80.00	Drove charred stake; raised mound of earth, with pits, etc., as per instructions, for Cor. to Secs. 9, 10, 15 & 16.
	Drove alder stake, 2 ft. long, 2 ins. sq., in S.E. pit.
	Land; rolling.
	Soil; 1st rate. Good grass.
<hr/>	
	E. on random line bet. Secs. 10 & 15.
40.00	Set temp. $\frac{1}{4}$ Sec. Cor.
80.00	Intersect N. & S. line, 7 lks. S. of Cor.
	S. 89°57'W. on true line.
40.00	Drove charred stake; raised mound of earth, with pits, etc., as per instructions, for $\frac{1}{4}$ Sec. Cor.
80.00	The Cor.
	Land; rolling.
	Soil; 1st rate. Good grass.
<hr/>	
	N. bet. Secs. 9 & 10.
	Var. 21°15'E.
40.00	Drove charred stake; raised mound of earth, with pits, etc., as per instructions, for $\frac{1}{4}$ Sec. Cor.
80.00	Drove charred stake; raised mound of earth, with pits, etc., as per instructions, for Cor. to Secs. 3, 4, 9 & 10.
	Drove willow stake, 2 ft. long, 2 ins. sq., in S.E. pit.
	Land; rolling.
	Soil; 1st rate.
<hr/>	
	E. on random line bet. Secs. 3 & 10.
40.00	Set temp. $\frac{1}{4}$ Sec. Cor.
80.00	Intersect N. & S. line at Cor.
	W. on true line.
40.00	Drove charred stake; raised mound of earth, with pits, etc.,