

Subdivisional Lines, T 5 N R 31 E W M.

Chains	as per instructions, for $\frac{1}{4}$ Sec. Cor.
80.00	The Cor. Land; rolling. Soil; 1st rate.
	N. on random line bet. Secs. 3 & 4. Var. 21°30'E.
40.00	Set temp. $\frac{1}{4}$ Sec. Cor.
75.75	Intersect N. Bdy. of Tp., 420 lks. E. of Cor. S. 3° E. on true line.
35.75	Drove charred stake; raised mound of earth, with pits, etc., as per instructions, for $\frac{1}{4}$ Sec. Cor.
75.75	The Cor. Land; gently rolling. Soil; 2nd rate. Oct. 28th, 1874.
	N. bet. Secs. 32 & 33.
40.00	Set basalt stone, 15 x 8 x 5, 7 ins. in ground, for $\frac{1}{4}$ Sec. Cor.
67.00	Spring Water Canyon, course N.W.
80.00	Set basalt stone, 18 x 6 x 6, 9 ins. in ground, for Cor. to Secs. 28, 29, 32 & 33. Land; rolling. Soil; 1st rate. Good grass.
	E. on random line bet. Secs. 28 & 33.
40.00	Set temp. $\frac{1}{4}$ Sec. Cor.
80.80	Intersect N. & S. line, 90 lks. N. of Cor. N. 89° 21' W. on true line.
40.40	Drove charred stake; raised mound of earth, with pits, etc., as per instructions, for $\frac{1}{4}$ Sec. Cor.
80.80	The Cor. Land; rolling. Soil; 1st rate. Good grass.