

Subdivisional Lines, T 5 N R 32 E W M.

Chains.	
	N. bet. Secs. 13 & 14.
	Var. 21°30'E.
40.00	Drove charred stake & raised mound of earth, with pits, etc., as per instructions for $\frac{1}{4}$ Sec. Cor.
80.00	Drove charred stake & raised mound, with pits, etc., as per instructions, for Cor. to Secs. 11, 12, 13 & 14.
	Drove willow stake, 2 ft. long, 2 ins. sq., in S.E. pit.
	Land; rolling.
	Soil; 1st rate. Good grass.
	E. on random line bet. Secs. 12 & 13.
40.00	Set temp. $\frac{1}{4}$ Sec. Cor.
80.49	Intersect E. Bdy. of Tp., 140 lks. S. of Cor. S. 89° W. on true line.
40.25	Drove charred stake & raised mound of earth, with pits, etc. as per instructions, for $\frac{1}{4}$ Sec. Cor.
80.49	The Cor.
	Land; rolling.
	Soil; 1st rate. Good grass.
	Note: See resurvey of Ext. Bdy. of this Tp. Nov. 2, 1874.
	N. bet. Secs. 11 & 12.
	Var. 21°30'E.
40.00	Drove charred stake & raised mound of earth, with pits, etc., as per instructions, for $\frac{1}{4}$ Sec. Cor.
80.00	Drove charred stake & raised mound, with pits, etc., as per instructions, for Cor. to Secs. 1, 2, 11 & 12.
	Drove willow stake, 2 ft. long, 2 ins. sq., in S.E. pit.
	Land; rolling.
	Soil; good. Good grass.
	E. on random line bet. Secs. 1 & 12.
40.00	Set temp. $\frac{1}{4}$ Sec. Cor.