

## Subdivisional Lines, T 5 N R 32 E W M.

Chains	
80.00	Intersect E. Bdy. of Tp., 230 lks. S. of Cor. S.88°21' W. on true line
40.00	Drove charred stake and raised mound of earth, with pits, etc., as per instructions, for $\frac{1}{4}$ Sec. Cor.
80.00	The Cor. Land; rolling. Soil; 1st rate.
N. on random line bet. Secs. 1 & 2. Var.21°30'E.	
40.00	Set temp. $\frac{1}{4}$ Sec. Cor.
83.70	Intersect N. Bdy. of Tp., 84 lks. E. of Cor. S.36° E. on true line.
43.70	Drove charred stake and raised mound of earth, with pits, etc., as per instructions, for $\frac{1}{4}$ Sec. Cor.
74.00	Juniper Canyon, course W.
83.70	The Cor. Land; rolling. Soil; 1st rate. Note: See resurvey of Ext. Bdy. of this Tp.
N. bet. Secs. 34 & 35.	
40.00	Drove charred stake and raised mound of earth, with pits, etc., as per instructions, for $\frac{1}{4}$ Sec. Cor.
80.00	Drove charred stake and raised mound of earth, with pits, etc., as per instructions, for Cor. to Secs. 26, 27, 34 & 35. Drove alder stake, 2 ft. long, 2 ins. sq., in S.E. pit. Land; rolling. Soil; 1st rate. Good grass.
E. on random line bet. Secs. 26 & 35.	
40.00	Set temp. $\frac{1}{4}$ Sec. Cor.
80.70	Intersect N. & S. line, 62 lks. S. of Cor.