

Subdivisional Lines, T 5 N R 32 E W M.

Chains	etc., as per instructions, for $\frac{1}{4}$ Sec. Cor.
80.85	The Cor. Land; rolling. Soil; 1st rate. Good grass.  Nov. 6th, 1874.
	N. bet. Secs. 15 & 16.  Var. 21°30'E.
40.00	Drove charred stake, and raised mound of earth, with pits, etc., as per instructions, for $\frac{1}{4}$ Sec. Cor.
80.00	Drove charred stake and raised mound of earth, with pits, etc., as per instructions, for Cor. to Secs. 9, 10, 15, and 16.  Drove willow stake, 2 ft. long, 2 ins. sq., in S.E. pit. Land; rolling. Soil; 1st rate. Good grass.
	E. on random line bet. Secs. 10 & 15.
40.00	Set temp; $\frac{1}{4}$ Sec. Cor.
80.80	Intersect N. & S. line, 160 lks. N. of Cor. N. 88°51' W. on true line.
40.40	Drove charred stake and raised mound of earth, with pits, etc., as per instructions, for $\frac{1}{4}$ Sec. Cor.
80.80	The Cor. Land; rolling. Soil; 1st rate. Good grass.
	N. bet. Secs. 9 & 10.  Var. 21°30'E.
40.00	Drove charred stake and raised mound of earth, with pits, etc., as per instructions, for $\frac{1}{4}$ Sec. Cor.
80.00	Drove charred stake, and raised mound of earth, with pits, etc., as per instructions, for Cor. to Secs. 3, 4, 9 & 10.