

Subdivisional Lines, T 5 N R 32 E W M.

Chains	
80.80	Intersect N. & S. line, 70 lks. N. of Cor. N.89°30' W. on true line.
40.40	Drove charred stake and raised mound of earth, with pits, etc., as per instructions, for $\frac{1}{4}$ Sec. Cor.
67.80	Bed of ravine, course N.W. Spring in ravine, 50 lks. N. of line.
80.80	The Cor. Land; rolling. Soil; 1st rate. Good grass.
N. bet. Secs. 8 & 9. Var.21°15' E.	
11.00	Ravine, course W.
40.00	Drove charred stake and raised mound of earth, with pits, etc., as per instructions, for $\frac{1}{4}$ Sec. Cor.
80.00	Drove charred stake and raised mound of earth, with pits, etc., as per instructions, for Cor. to Secs. 4, 5, 8 & 9. Drove willow stake, 2 ft. long, 2 ins. sq., in S.E.pit. Land; rolling. Soil; 1st rate. Good grass.
E. on random line bet. Secs. 4 & 9.	
40.00	Set temp. $\frac{1}{4}$ Sec. Cor.
80.70	Intersect N. & S. line, 38 lks. N. of Cor. N.89°44' W. on true line.
40.35	Drove charred stake and raised mound of earth, with pits, etc., as per instructions, for $\frac{1}{4}$ Sec. Cor.
80.70	The Cor. Land; rolling. Soil; 1st rate. Good grass.
N. bet. Secs. 4 & 5, on random line. Var.21°30'E.	
40.00	Set temp. $\frac{1}{4}$ Sec. Cor.