

Subdivisional Lines, T 5 N R 32 E W M.

Chains	etc., as per instructions, for $\frac{1}{4}$ Sec. Cor.
79.47	The Cor. Land; rolling. Soil; 1st rate.
N. bet. Secs. 19 & 20. Var. 21°30'E.	
40.00	Drove charred stake and raised mound of earth, with pits, etc., as per instructions, for $\frac{1}{4}$ Sec. Cor.
80.00	Drove charred stake and raised mound of earth, with pits, etc., as per instructions, for Cor. to Secs. 17, 18, 19 and 20. Drove willow stake, 2 ft. long, 2 ins. sq., in S.E. pit. Land; rolling. Soil; 1st rate. Good grass.
E. on random line bet. Secs. 17 & 20.	
40.00	Set temp. $\frac{1}{4}$ Sec. Cor.
80.56	Intersect N. & S. line, 45 lks. S. of Cor. S. 89°41' W. on true line.
40.28	Drove charred stake and raised mound of earth, with pits, etc., as per instructions, for $\frac{1}{4}$ Sec. Cor.
80.56	The Cor. Land; rolling. Soil; 1st rate. Good grass. Nov. 10th, 1874.
W. on random line bet. Secs. 18 & 19.	
40.00	Set temp. $\frac{1}{4}$ Sec. Cor.
80.54	Intersect W. Bdy. of Tp., 353 lks. S. of Cor. S. 87°29' E. on true line.
40.54	Drove charred stake and raised mound of earth, with pits, etc., as per instructions, for $\frac{1}{4}$ Sec. Cor.
80.54	The Cor. Land; rolling. Soil; 1st rate.